Citi Trends sign drawings

Revision #1 - 5/18/21

Original Drawing 4/21/21

Scope of job:
- Supply and install
(2) building signs,
1 on front and
1 on back wall.

4'6" LED lighted channel letters
on a 5'6" x 22'6" powder coated aluminum back-panel
123.75 sq.ft.

Citi Trends space 100' wide

4'6" LED lighted channel letters
on a 5'6" x 22'6" powder coated aluminum back-panel
123.75 sq.ft.

Back wall - 102' wide

NOTE:
- Existing marks/holes from previous signage will be repaired and facia painted as needed
- All signage will be professionally installed without exposed hardware, wiring, etc.
- All required permits will be obtained and electrical work done by certified electrician.
- Time clock will be installed and hooked to sign curcuit by certified electrician
- Work will be coordinated and all required documents will be provided to mall prior to installation.
- UL labels will be applied to not be easily seen from the ground but still accessible to inspector.
- See attached spec sheet with details (trim cap matches returns, etc.)

Citi Trends #783
Southaven Town
Center S/C

135 Town Sq. Blvd.
Southaven MS 38671

BrandRite® SIGN COMPANY INC.

803-533-7446
313 John C Calhoun Drive
Orangeburg SC 29115
Linford Oberholtzer
lin@brandritesign.com
Mobile 803-707-4512